

B - 2 : Bill of Material for Construction of Boundary Wall around existing 11 KV Sub Station

Sl. No.	Item Description	Unit	Rate (In Rs.)	Estimated Qty per S/s	No. of S/s Quoting for	Value (in Rs.)
(1)	(2)	(3)	(4)	(5)	(6)	(7)=(4)x(5)x(6)
1	Construction of 230 mm thick brick masonry, 1.5 m high Boundary Wall (from GL). The wall shall be plastered, both inside and outside with 18 mm thick cement mortar (1:4 mix). The Boundary Wall shall be painted with two coats of white wash with lime.	Run. Mtr		16.5		
2	Supply and Installation of Double Leaf MS Gate of height 1.5 m height x 1.5 m width, made up of 30x30x6 angle and 25x6 Flat as per approved Drawing. The gate shall be painted with two coat of approved primer with two coats of approved epoxy paint.	Lot		1		
3	Construction of 2 no.s Concrete Column of size 300x300x2000 mm with RCC Concreting including Re-Inforced Steel (1:3:6) for fixing of the Gate.	Cum		0.36		
4	Unit Rate may be quoted for the following items					
i	Gravel Spreading (80 mm thick)	Sq. Mtr				
ii	Filling of Borrowed Earth	Cum				
iii	Filling of Borrowed Sand & Morrum	Cum				

Note : For computation of Bid Security, the unit rates quoted for items under srl. no.4 (i to iii) need not be considered.