

A - 5 : Bill of Material for Construction of New LT Line with AB Cable

Sl. No.	Item Description	Unit	Estimated Qty/ KM of Line	Rate (In Rs.)	Km. Quoting for	Value (in Rs.)
(1)	(2)	(3)	(4)	(5)	(6)	(7)=(4)x(5)x(6)
A	Laying of following sizes of AB Cable including Eye Hook, Pole Clamp, Suspension / Strain Fitting.					
1	3 x 35 + 1 x 25 MM ²	Km.	1			
2	3 x 50 + 1 x 35 MM ²	Km.	1			
B	Installation of following Items					
1	8 Mtr x 200 Kg PSC Pole with Base Plate including Brickbatting	No.s	22			
2	Coil Earthing	No.s	5			
3	LT Stay Set Complete including Clamp, LT Stay Insulator	No.s	10			
4	Service Distribution Box including Service Connection to existing consumers.					
a	4 Way	No.s	18			
b	8 Way	No.s	33			
c	12 Way		9			
5	Piercing Connector (AB Cable to SDB)	No.s	12			
6	Neutral Connector	No.s	18			

